BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Name of the Work : Improvements to Roads and Drains at Hegdenagara Main Road Left Side Cross Roads in Ward No. 06, Hegdenagara Village Limits.

Sl. No.	Approved Qty.	Description	Unit	Approved Rates	
				In Figures	In Words
1	**1290.48**	KSRRB 300-2. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. etc complete as per specifications and directions of engineer in charge of the work	Cum	90.72	Rupees Ninety And Paise Seventy Two Only
2	**3735.60**	Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	50.11	Rupees Fifty And Paise Eleven Only
3	**2988.48**	Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	70.04	Rupees Seventy And Paise Four Only
4	**709.50**	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	343.44	Rupees Three Hundred Forty Three And Paise Forty Four Only
5	**6226.00**	KSRRB 500-3: Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications. etc complete as per specifications and directions of engineer in charge of the work	Sqm	72.79	Rupees Seventy Two And Paise Seventy Nine Only
6	**1381.04**	Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications etc complete as per specifications and directions of engineer in charge of the work	Cum	1121.04	Rupees One Thousand One Hundred Twenty One And Paise Four Only
7	**6226.00**	KSRRB 500-1.1 : Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. etc complete as per specifications and directions of engineer in charge of the work	Sqm	10.53	Rupees Ten And Paise Fifty Three Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KHIDL BBMP, Bangalore

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Rates	
				In Figures	In Words
8	**6226.00**	KSRRB 500-5: providing and applying primer coat from 12.2 to 14.6kg per 10 sqm for surfaces of high porosity over prepared surface of granular base with cut back M.C.-70 or any other bitumen mixed with diesel at 13 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. etc complete as per specifications and directions of engineer in charge of the work	Sqm	142.07	Rupees One Hundred Forty Two And Paise Seven Only
9	**155.65**	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specificationsWith 60/70 grade bitumen using 40-60 HMP, etc complete as per specifications and directions of engineer in charge of the work	Cum	9981.36	Rupees Nine Thousand Nine Hundred Eighty One And Paise Thirty Six Only
10	**1290.48**	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	72.71	Rupees Seventy Two And Paise Seventy One Only

I am prepared to execute the above mentioned work written by me in Schedule - B

Contractor Signature
Reg. No.
Postal Address

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92